

## Phytochemical Screening and Antioxidant Properties of Coagulants and Soft Cheese Produced from Goat Milk Using Different Biocoagulants of Plant Origin

A. O. Ogunlade<sup>1\*</sup>, V. O. Oyetayo<sup>2</sup> and A. O. Ojokoh<sup>2</sup>

<sup>1</sup>Department of Food Technology, Federal Polytechnic, Ado-Ekiti, P.M.B 5351, Ekiti State, Nigeria.

<sup>2</sup>Department of Microbiology, Federal University of Technology, Akure, P.M.B 704, Ondo State, Nigeria.

### Authors' contributions

This work was carried out in collaboration between all authors. Author AOOgunlade designed the study, performed the statistical analysis, wrote the protocol, and wrote the first draft of the manuscript. Authors VOO and AOOjokoh managed the analyses of the study. Author AOOgunlade managed the literature searches. All authors read and approved the final manuscript.

### Article Information

DOI: 10.9734/AFSJ/2019/45699

#### Editor(s):

(1) Dr. Aneta Popova, Chief assistant Professor, Department of Catering and Tourism, University of Food Technologies, Bulgaria.

#### Reviewers:

(1) F. Solano, University of Murcia, Spain.

(2) Tomislav Pogačić, University of Zagreb, Croatia.

(3) Érica Resende Oliveira, Federal University of Lavras, Brazil.

Complete Peer review History: <http://www.sdiarticle3.com/review-history/45699>

Original Research Article

Received 08 October 2018  
Accepted 26 December 2018  
Published 18 January 2019

### ABSTRACT

The nutritional importance and easy accessibility of soft cheese has made it indispensable. This study assessed the phytochemical constituents and the effects of antioxidant of biocoagulants used in soft cheese produced from goat milk. Different biocoagulants such as *Calotropis procera*, *Carica papaya*, lemon juice and steep water from cereals (maize, millet, and sorghum) were used. The results of the antioxidant properties revealed that *Carica papaya* had the highest ferric reducing property and displayed better DPPH scavenging activity of 14.94 mg AAE/g and 10.82%, respectively, when compared with other biocoagulants. Also, the results of phytochemical screening revealed that cheese coagulated with *Carica papaya* displayed the highest DPPH scavenging activity (1.93%) compared with other cheese samples. Cheese coagulated with lemon juice had the highest phenol content (19.88 mgGAE/100g) and also displayed the highest ferric

\*Corresponding author: Email: ayoyemi19@gmail.com;

reducing property (10.31mg AAE/g). Cheese coagulated with steep water from millet had the highest flavonoid content (0.20 mgGAE/100g) and cheese coagulated with *Calotropis procera* had the highest alkaloid content (13.42 (mgGAE/100 g). Therefore, cheese produced from goat milk coagulated with *Carica papaya* or lemon juice may be incorporated into the daily diet because of its high phenolic content which can improve the health status of the consumers. It also possesses some natural antioxidant compounds, which can effectively scavenge free radicals.

**Keywords:** *Phytochemical; antioxidants; soft cheese; goat milk.*

## 1. INTRODUCTION

Soft cheeses are usually made from raw milk obtained from animal husbandry. They vary widely in nutritional composition, depending on whether they belong to the ripened or unripened varieties, as well as the biocoagulants used. Wara is a type of unripened soft cheese obtained from cow milk, however, milk can also be gotten from other animals such as goat, sheep, camel e.t.c. Goat often referred to as the “poor man’s cow” due to his great contribution to the health and nutrition of the landless and rural people [1]. Goat produces milk which differs from cow or human milk in having better digestibility, alkalinity and buffering capacity [2]. It contains vitamins, minerals, trace elements, electrolytes, enzymes, proteins, and fatty acids that are easily assimilated by the body [3]. Therefore awareness about advantage of consumption of goats milk should be popularized so that production and utilization of goat’s milk could be enhanced [3].

Coagulating agents has been greatly used in the coagulation of milk for the production of cheese [4]. Conventionally, soft cheese is prepared by coagulating the fresh milk with the leaf extract of Sodom apple (*Calotropis procera*). Other coagulants, such as lemon juice and *Carica papaya* can also be used. Medicinal plants such as *Calotropis procera* and *Carica papaya* are the oldest form of healthcare known to mankind and have been used for centuries as remedies for human and animal diseases as they contain phytochemicals of therapeutic value [5]. These medicinal plants have many pharmacological effects such as antimicrobial, anti-inflammatory, analgesic, anticancer, anti-angiogenic, immunological, antidiabetic, cardiovascular, gastroprotective, hepatic protective, renal protective, antidiarrheal, antioxidant, anticonvulsant as well as enhancement of wound healing [6,7]. Rennet is a coagulant of animal origin which served as alternative for the coagulation of raw milk from cow for soft cheese production. The use of rennet is being frowned at

due to the high cost, some vegetarians abhor it and also the issue of religion (Judaism and Islam) [8]. However, if *Calotropis procera* plant should go into extinction due to unfavorable weather, or if there is higher demand because of its wide range of usefulness without adequate replacement, it will therefore be necessary for cheese makers to source for alternative coagulants of plant origin which are cheaper, easily accessible and add value to the final cheese product. The objective of this work is therefore to assess the phytochemical and antioxidant properties of the biocoagulants and soft cheese samples produced from goat milk using different coagulants.

## 2. MATERIALS AND METHODS

### 2.1 Sampling

The raw milk sample was collected from goats at Aba Baba Medinat, a Fulani farm settlement along Afao road (Ado-Ekiti, Nigeria). It was collected aseptically and subsequently transferred to the laboratory for analysis using an ice pack.

### 2.2 Collection of Coagulants

The leaves of *Carica papaya* and *Calotropis procera* were collected from Erifun community around The Federal Polytechnic, Ado-Ekiti, Nigeria. Authentications of the Plants were done at the Department of Plant Science and Biotechnology, Ekiti State University, Ado-Ekiti, Nigeria. The voucher specimens of UHAE 2018/022 for *Carica papaya* and UHAE 2018/023 for *Calotropis procera* have been deposited at the University herbarium. Other sources of biocoagulants such as lemon fruits were purchased from Oba market, a local market in Ado Ekiti Metropolis (Nigeria, West Africa). Steep water from maize, sorghum and millet were produced by soaking the well sorted and washed grains in water for 3 days and then milled, the milled grain were later steeped again at room temperature for 2 days and the effluent was

collected and preserved in the refrigerator at 4°C to be used as biocoagulant.

### 2.3 Preparation of Coagulants

Ten grams (10 g) of sodom apple leaves (*Calotropis procera*) were thoroughly washed with one litre of clean water. The extract was obtained by crushing the leaves and stems of *Calotropis procera* plant. A clean muslin cloth was used to sieve the mashed leaves to get the pure extract which was poured into a clean bowl and labeled as sample A.

Pawpaw leaves (*Carica papaya*): 10 g of leaves of *Carica papaya* were washed thoroughly and mashed in order to get the extract using a mortar and pestle. A clean muslin cloth was used to sieve and separate the extract from the macerated leaves to get a pure extract. This was poured into a clean bowl and labeled as sample B.

Sorghum, Millet and Maize: These grains were bought from the local market in Ado Ekiti and were sorted to remove debris which might lead to contamination of the products. The grains were then washed and soaked in clean water separately for 3 days, after which it was milled with the aid of milling machine and was left for another 2 days at room temperature. The steep water was kept refrigerated (4°C) and used as biocoagulants until analysis. These were labeled as samples C, D and E respectively.

Lemon fruits were brought from the local market and washed. The fruits were cut and the juice was squeezed into a bottle ready to be used as coagulant. This was labeled as sample F.

### 2.4 Production of Soft Cheese

Raw milk (1000 mL) from goat was heated slowly at 45-50°C for 30-40 min. The milk was stirred gently during the heating process. An aliquot of 4 mL of the leaf extract of *Calotropis procera* and *Carica papaya*, lemon juice and steep water from different grains were added separately to the warm milk (1000 mL) and the mixture was heated with intermittent stirring to about 95°C and was kept at this temperature until coagulation was achieved. The heating was stopped after the separation of curd and whey. The sign of coagulation was observed within 10 - 15 min from the time that the coagulants were added. It was transferred into a small, previously sterilized, raffia basket to facilitate whey drainage

of the cheese and allow the formation of its characteristic shape. When the cheese was firm enough, it was removed from the raffia basket and placed inside a covered plastic container and kept refrigerated (4°C) until analysis.

### 2.5 Phytochemical Screening of Soft Cheese Sample

#### 2.5.1 Quantitative phytochemical screening

##### 2.5.1.1 Determination of total phenolic content

The samples (100 mg) were weighed accurately and dissolved in 100 mL of triple distilled water (TDW). This solution (1 mL) was transferred to a test tube, then 0.5 mL of the Folin Ciocalteu's reagent (2 mol/L) and 1.5 mL of Na<sub>2</sub>CO<sub>3</sub> (20%) solution was added, and ultimately, the volume was made up to 8 mL with TDW followed by vigorous shaking and finally allowed to stand for 2 h after which the absorbance was taken at 765 nm. Gallic acid was used as a standard positive control. The calibration curve was built as 0.02, 0.04, 0.06, 0.08, and 0.10 mg gallic acid/100 g, that was prepared in 80% (v/v) methanol. The total phenol content in the sample was calculated from the standard curve and the results expressed as gallic acid equivalent (GAE) per 100 g dry weight (d.b.) of the sample [9].

##### 2.5.1.2 Determination of total Flavonoids

Aluminium chloride colorimetric method was used for flavonoids determination. 100 µL of the solubilized wara sample in methanol (10 mg/mL) was mixed with 100 µL of (20 %) aluminum trichloride in methanol and a drop of acetic acid, and then diluted with methanol to 5 mL. The absorption at 415 nm was read after 40 min with a UV/Visible spectrophotometer. Blank samples were prepared from 100 mL of solubilized cheese sample and a drop of acetic acid, and then diluted to 5 mL with methanol. The absorption of standard routine solution (0.5 mg/mL) in methanol was measured under the same conditions.

##### 2.5.1.3 Determination of total alkaloids

This was done by the alkaline precipitation gravimetric method proposed by [10] and later described by [11]. Cheese sample (5 g) was weighed into a 250 mL beaker and dispersed in 200 mL of 10% acetic acid solution in ethanol to form a ratio of 1:10 (10%). The mixture was allowed to stand for 4 h at 28°C. It was later paper filtered (Whatman No. 42). The filtrate was

concentrated in a water bath (100°C) to one quarter of its original volume by evaporation and treated with drop wise addition of concentrated aqueous NH<sub>4</sub>OH until the alkaloid was precipitated. The precipitate was collected on a pre- weighed filter paper, washed with 1% ammonia solution. It was then oven-dried at 80°C to a constant weight. The percentage yield of alkaloid was calculated from the weights of precipitate and that of the original sample.

## 2.6 Determination of Antioxidant Capacity

### 2.6.1 Determination of Ferric Reducing Antioxidant Power Assay (FRAP)

The reducing power of the samples was determined by assessing the ability of the soft cheese sample to reduce FeCl<sub>3</sub> solution according to the method described [12]. A 2.5 mL aliquot of each solubilized cheese samples was mixed with 2.5 mL of 200 mM sodium phosphate buffer (pH 6.6) and 2.5 mL of 1% potassium ferricyanide. The mixture was incubated at 50°C for 20 min, and then 2.5 mL of 10% trichloroacetic acid was added. This mixture was centrifuged at 650 rpm for 10 min. The supernatant was collected and 5 mL aliquot of each solubilized sample was mixed with an equal volume of water and 1 mL of 0.1% ferric chloride. The absorbance was measured at 700nm. The ferric reducing antioxidant property of soft cheese sample was subsequently calculated using ascorbic acid equivalent as a standard.

### 2.6.2 Scavenging effect on 1, 1 -diphenyl-2-picrylhydrazyl (DPPH)

The DPPH (2,2-difenil-1-picrilhidrazil) free radical-scavenging capacity was estimated using the method [13], later modified by [14] with minor suitable modifications. Soft cheese samples of different concentrations (1.0 mL) were mixed with 5.0 mL of 0.4 mM DPPH in methanol. The mixture was incubated at room temperature for 30 min in dark. The control contains only DPPH solution in methanol instead of sample while methanol served as the blank. Absorbance was noted at 517 nm by using UV-visible spectrophotometer. The capacity of scavenging free radicals was calculated as:

$$\text{Scavenging activity (\%)} = \frac{[Ab - (As-Abs)]}{Ab} \times 100$$

Where, Ab is absorbance of blank, Abs is the absorbance of sample + blank, and As is the absorbance of sample.

Sample concentration causing 50% inhibition (IC<sub>50</sub>) was calculated from the graph, plotting the % inhibition against sample concentration.

## 2.7 Statistical Analysis

All analyses were carried out in triplicate. Statistical significance was established using one-way analysis of variance (ANOVA), and data were reported as the mean ± standard deviation. Mean comparison and separation was done using Duncan Multiple range (DMR) test at p ≤ 0.05. Statistical analysis was carried out using the SPSS 16.0 statistical package.

## 3. RESULTS AND DISCUSSION

### 3.1 Quantitative Phytochemical Composition of Cheese Produced from Goat Milk Using Different Biocoagulants

The quantitative phytochemical composition of cheese produced from goat milk using different biocoagulants are presented in Table 1. Cheese coagulated with lemon juice had the highest phenol content. Cheese coagulated with steep water from millet had the highest flavonoids content and cheese coagulated with *Calotropis procera* had the highest alkaloids content. While, the lowest phenol content (15.39 mgGAE/100 g) was found for the goat milk coagulated with *Calotropis procera*; flavonoid content (0.06 mgGAE/100 g) was observed for goat milk coagulated with lemon juice, and concerning the alkaloids, the lowest content (7.64 mgGAE/100 g) was for the goat milk coagulated with millet steep water.

### 3.2 FRAP assay

The FRAP of the biocoagulants and soft cheese produced from goat milk using different biocoagulants is presented in Figs. 1 and 2, respectively. The values obtained for FRAP ranged from 1.43 to 14.94mg AAE/g for biocoagulants and from 7.74 to 10.31mg AAE/g for the soft cheese samples.

### 3.3 DPPH Scavenging Activity

The scavenging activity of the biocoagulants and soft cheese samples against DPPH free radicals are presented in Figs. 3 and 4, respectively. The scavenging activity of biocoagulants against DPPH ranged from 1.37 to 10.82%, while the

results of soft cheese from goat milk ranged from 1.56 to 1.93%.

The presence of phenols indicates that the cheese may be able to achieve multiple activities such as antioxidant, anticarcinogenic and anti-inflammatory [15]. Alkaloids are the most significant compounds that play a metabolic role in the living systems and are involved in the protective function in animals. Pure isolated alkaloids and the synthetic derivatives are used as basic medicinal agents because of their analgesic, antispasmodic and bacterial properties [16]. Flavonoids have been used against the cancer causing tumors and it inhibits the promotion of growth and progression of tumors [17]. Phenols and phenolic compounds have been extensively used in disinfection and remains the standard with which other bactericides are compared [18]. These


phytochemicals and phenolic compounds have been shown to contribute immensely to the medicinal and nutritional quality of plant and plant products [19]. It has been reported that intake of these bioactive constituents to an extent has protective and therapeutic effects essential to preventing diseases and maintaining a state of wellbeing [20].

The amount of phytochemicals found in the cheese samples was quantitatively determined by standard procedures (Table 1). The presence of the phytochemical constituents, such as alkaloids, flavonoids, phenols in the cheese samples makes it a good source of beneficial bioactive compound that can improve the health status of the consumers. Flavonoids can function as direct antioxidants and free radical scavengers, and have the capacity to modulate enzymatic activities and inhibit cell proliferation

**Table 1. Quantitative phytochemical composition (mgGAE/100 g)\* of soft cheese produced from goat milk using different biocoagulants**


Cheese samples	Phenols	Flavonoids	Alkaloids
GCPR	15.39± 0.14 <sup>f</sup>	0.16±0.01 <sup>a</sup>	13.42±0.01 <sup>a</sup>
GCP	17.18± 0.16 <sup>d</sup>	0.08 ±0.01 <sup>c</sup>	9.23±0.01 <sup>e</sup>
GLJ	19.88±0.01 <sup>a</sup>	0.06±0.01 <sup>d</sup>	9.78± 0.01 <sup>d</sup>
GSO	17.87±0.02 <sup>c</sup>	0.09 ±0.00 <sup>c</sup>	10.82± 0.00 <sup>c</sup>
GMI	16.35±0.09 <sup>e</sup>	0.20±0.01 <sup>a</sup>	7.64±0.01 <sup>f</sup>
GMA	18.57± 0.02 <sup>b</sup>	0.09± 0.01 <sup>c</sup>	11.83± 0.02 <sup>b</sup>

Key: GSO – goat milk coagulated with steep water from sorghum, GMA - goat milk coagulated with steep water from maize, GMI - goat milk coagulated with steep water from millet, GLJ - goat milk coagulated with lemon juice, GCPR - goat milk coagulated with *Calotropis procera*, GCP - goat milk coagulated with *Carica papaya*. \*Values are means ± standard deviation (n=3). Means with different letters within a column are significantly different. (P < 0.05)




**Fig. 1. Ferric reducing antioxidant power of biocoagulants**

CPR - *Calotropis procera* extract, CP - *Carica papaya* extract, LJ - lemon juice, MA - steep water from maize, MI - steep water from millet, SO - steep water from sorghum



**Fig. 2. Ferric reducing antioxidant power of local cheese produced from goat milk using different bio-coagulants**

GSO – goat milk coagulated with steep water from sorghum, GMA - goat milk coagulated with steep water from maize, GMI - goat milk coagulated with steep water from millet, GLJ - goat milk coagulated with lemon juice, GCPR - goat milk coagulated with *Calotropis procera*, GCP - goat milk coagulated with *Carica papaya*.




**Fig. 3. Scavenging activity of bio-coagulants used in the production of local cheese on DPPH free radical**

SO- steep water from sorghum, MA- steep water from maize, MI- steep water from millet, LJ- lemon juice, CPR- *Calotropis procera* extract, CP- *Carica papaya* extract.

[21]. The highest alkaloids recorded in soft cheese produced from *Calotropis procera* might be due to the fact that *Calotropis procera* contains bioactive compounds such as alkaloids, which might have been introduced into the cheese sample during processing [5], thereby making the final cheese product highly nutritive. The use of bio-coagulants such as *Calotropis procera* has been encouraged because it is readily available, cheaper, and safe for consumption as against the use of rennet which is very costly.

Extract from *Carica papaya* (14.94mg AAE/g) and soft cheese produced with lemon juice (10.31mg AAE/g sample) showed the highest ferric reducing property when compared with others ( $p < 0.05$ ). It has been reported that the antioxidant activity of plant material was well correlated with the content of their phenolic compounds [22,23]. The ability of the bio-coagulants and the soft cheese to scavenge DPPH radicals is presented in Figs. 3 and 4, respectively. *Carica papaya* displayed better DPPH scavenging activity (10.82%) when



**Fig. 4. Scavenging activity of local cheese produced from goat milk using different biocoagulants**

**KEY:** GSO – goat milk coagulated with steep water from sorghum, GMA - goat milk coagulated with steep water from maize, GMI - goat milk coagulated with steep water from millet, GLJ - goat milk coagulated with lemon juice, GCPR - goat milk coagulated with *Calotropis procera*, GCP - goat milk coagulated with *Carica papaya*.

compared with other biocoagulants (1.37%, 1.41%, 1.42%, 1.97%, 7.72%) while soft cheese coagulated with *Carica papaya* displayed better DPPH scavenging activity (1.93%) when compared with other cheese samples (1.56%, 1.71%, 1.78%, 1.79%, 1.86%). Coagulants such as *Carica papaya* have been reported to be a rich antioxidants source due to the presence of phenolic group and carotenoids which can scavenge free radicals [24,25]. The results showed that the soft cheese and the biocoagulants possess natural antioxidant compounds, which can effectively scavenge free radicals.

#### 4. CONCLUSIONS

The results of phytochemical screening revealed that the soft cheese produced from goat milk using different biocoagulants contain appreciable amount of phenols, alkaloids, and flavonoids. Goat milk coagulated with lemon juice presented the highest phenol content; cheese coagulated with millet steep water had the highest flavonoid content, while *Calotropis procera* coagulated cheese had the highest alkaloid content. The addition of the biocoagulants increased the bioactive content of cheese samples. *Carica papaya* displayed better DPPH scavenging activity when compared with other samples, and soft cheese produced from goat milk coagulated with *Carica papaya* was able to scavenge free radical better than other samples.

#### ACKNOWLEDGEMENTS

Authors thank all the participants who took part in this study; the authors gratefully appreciate Dr Ogunlade T.O, Dr Molehin Raphael and Mrs Aladejana for their contributions. The authors also thank the anonymous reviewers who helped to improve this paper.

#### COMPETING INTERESTS

Authors have declared that no competing interests exist

#### REFERENCES

1. Dresch J. A plea for the goat. Production Pastorale-et-Societe OAE. 1982;10:81-83.
2. Park Y. Hypo-allergenic and therapeutic significance of goat milk. Small Ruminant Research. 1994;14(2):151-159.
3. Kumar S, Kumar B, Kumar R, Kumar S, Khatkar S, Kanawjia SK. Nutritional features of goat milk. A review. Indian Journal of Dairy Science. 2012;65(4).
4. Chikpah SK, Teye M, Annor JAF, Teye GA. Potentials of Sodom apple (*Calotropis procera*) extract as a coagulant to substitute alum in soy cheese production in Ghana. Elixir International Journal of Food Science; 2014.
5. Ali EA. The constituents and pharmacological properties of *Calotropis procera*-An

- overview. International Journal of Pharmacy Review and Research. 2015;5(3):259-275.
6. Ahmed UAM, Zuhua S, Bashier NHH, Muafi K, Zhongping H, Yuling G. Evaluation of insecticidal potentialities of aqueous extracts from *Calotropis procera* ait. Against *Henosepilachna elaterii* rossi. Journal of Applied Science. 2006;6(1): 2466-2470.
  7. Yoganarasimhan SN. Medicinal plants of India. Regional research institute (Ay.) Bangalore, Tamil Ayurvedic uses and Pharmacological activities of *Calotropis procera* Linn. Asian Journal of Traditional Medicines. 2000;6(2):97.
  8. Roseiro LB, Babosa M, Ames JM, Wilbey RA. Cheese making with vegetable coagulants-the use of *Cynara* L for the production of bovine milk cheeses. International Journal of Dairy Technology. 2003;56(2):76-85.
  9. Singleton VL, Orthofer R, Lamuela-Raventos RM. Analysis of total phenols and other oxidation substrates and antioxidants by means of Folin-Ciocalteu reagent. Methods Enzymology. 1999;299: 152-178.
  10. Harborne JB. Phytochemical methods. Chapman and Hall Ltd., London. 1973;49-188.
  11. Mboso OE, Eyong EU, Odey MO, Osakwe E. Comparative phytochemical screening of *Ereromastax speciosa* and *Ereromastax polysperma*. Journal of National Production and Plant Resources. 2013;3(2)37-41.
  12. Benzie IFF, Strain JJ. The Ferric Reducing Ability of Plasma (FRAP) as a Measure of "Antioxidant Power": The FRAP assay. Analytical Biochemistry. 1996;239:70-76.
  13. Blois MS. Antioxidant determinations by the use of a stable free radicals. Nature. 1958;26:1199-1200.
  14. Brand-Williams W, Cuvelier ME, Berset C. Use of a free radical method to evaluate antioxidant activity. Lebensm. Wiss. u.-Technol. 1995;28.25-30.
  15. Asha K, Rasika CT, Nirmala RD, Jyoti PS. Analytical Biology Research. 2011;2(1): 176-180.
  16. Stray F. The natural guide to medicinal herbs and plants. Tiger Books International, London. 1998;12-16.
  17. Stevens JF, Hart HT, Hendriks H, Malingre TM. Alkaloids of some European and macaronesian diode and semepervivodeae (Crassulaceae). Phytochemistry. 1992;31: 3917-3924.
  18. Akinyeye AJ, Solanke EO, Adebisi IO. Phytochemical and antimicrobial evaluation of leaf and seed of *Moringa olifera* extract. International Journal of Research in Medicine and Health Sciences. 2014;4(6):2307-2083.
  19. Doughari HJ. Phytochemicals: Extraction methods, basic structures and mode of action as potential chemotherapeutic agents. In: Rao V, editor. Phytochemicals-A modern global perspective of their role in nutrition. In Tech. 2012;14.
  20. Boyer J, Liu RH. Apple phytochemicals and their health benefits. Nutr. J. 2004;3:1-15.
  21. Duthie G, Crozier A. Plant-derived phenolic antioxidants. Current Opinion in Lipidology. 2000;11:43-47.
  22. Velioglu YS, Mazza G, Gao L, Oomah BD. Antioxidant activity and total phenolics in selected fruits, vegetables, and grain products. Journal of Agricultural Food Chemistry. 1998;46:4113-4117.
  23. Eze FN, Airouyuwa OJ. Quantitative phytochemical evaluation of stem bark extracts of *Harungana madagascariensis*. British Journal of Pharmaceutical Research. 2014;4(17):2068-2074.
  24. Aravind G, Debjit Bhowmik, Duraivel S, Harish G. Traditional and medicinal uses of *Carica papaya*. Journal of Medicinal Plants Studies. 2013;1(1):7-15.
  25. Usman R, Khan A, Gul S, Rauf A, Muhammad N. Evaluation of *in vitro* antioxidant properties of selected medicinal plants. Middle-East Journal of Medicinal Plants Research. 2012;1(2):28-31.

© 2019 Ogunlade et al.; This is an Open Access article distributed under the terms of the Creative Commons Attribution License (<http://creativecommons.org/licenses/by/4.0>), which permits unrestricted use, distribution, and reproduction in any medium, provided the original work is properly cited.

Peer-review history:

The peer review history for this paper can be accessed here:  
<http://www.sdiarticle3.com/review-history/45699>